





VERSADRY TRACK SYSTEM



VERSADRY DRYWALL TRACK SYSTEM

Patented system allows the installation of drywall to sit 2 inches off the floor on a steel shelf. This shelf mitigates the wicking of water both during construction and the life of the building.

VERSADRY TRACK PROTECTS DRYWALL FROM WATER DAMAGE



Wall damage *without* Versadry



VERSADRY TRACK: 1 PIECE DESIGN (Ideal for new construction)

US PATENT 12,428,837

Thickness Nomenclature	Non-Rate Length	1 Hour Rated + Clip	2 Hour Rated + Clip	Min Base Metal Thickness (in)	Design Thickness (in)	Min Yield Strength (ksi)	Standard Galvanization	Web Sizes (in)
VDT1-18	Max 24'	Max 24' Length (10' Recommended)		0.0179"	0.0186"	33 ksi	G40	3-5/8", 4", 5.5", 6"
VDT1-30				0.0296"	0.0312"			

VERSADRY TRACK: 2 PIECE DESIGN (Ideal for retrofits)

US PATENT 8,596,019 | 10,487,497

Thickness Nomenclature	Non-Rate Length	1 Hour Rated	2 Hour Rated	Min Base Metal Thickness (in)	Design Thickness (in)	Min Yield Strength (ksi)	Standard Galvanization	Web Sizes (in)
VDT2-18	24'	10'	10'	0.0179"	0.0186"	33 ksi	G40	2 piece design. Any web size is possible
VDT2-30	12'	N/A	N/A	0.0296"	0.0312"			

VERSADRY DIMENSIONS

	Gypsum Ledge Height	Gypsum Ledge Width
Non-Rated	2.00"	0.688"
1 Hour Fire Rated	2.00"	0.688"
2 Hour Fire Rated	2.00"	1.295"

- KEEPS GYPSUM DRY
- IMPROVED FIRE RESISTANCE WITHOUT CAULK
- IMPROVED ACOUSTICAL PERFORMANCE
- ELEGANT FINAL FIT AND FINISHED APPEARANCE
- HELPS REDUCE MOLD GROWTH

VERSADRY TRACK CERTIFICATIONS:

FIRE RESISTANCE:

Independent accredited 3rd party tested per ASTM E119, consistent with the UL Wall Design U423 construction, to meet a 1 hour & 2 hour Fire Rating without caulk.

- The tested 1 hour fire rated wall construction consisted of: 18mil VersaDry Track, VersaDry Fire Clips, 1 layer of 5/8" Type X Gypsum, & 20ga 3-5/8" studs spaced 16"OC
- The tested 2 hour fire rated wall construction consisted of: 18mil VersaDry Track, VersaDry Fire Clips, 2 layers of 5/8" Type X Gypsum, & 20ga 3-5/8" studs spaced 16"OC
- VersaDry 1 piece design with clip at floor & ceiling passed ASTM E119 1-hour and 2-hour fire and hose stream test without caulk at Intertek certified independent 3rd party test lab.

NO CAULK NEEDED!

ACOUSTICAL PERFORMANCE:

3rd part tested per ASTM E90-09 and calculated per ASTM E413-16.

- STC = 45 for Non-Fire Rated 18mil VersaDry Track w/ 1 layer of 5/8" Type X Gypsum
- STC = 48 for Non-Fire Rated 18mil VersaDry Track w/ 1 layer of Impact Resistant Gypsum
- STC = 46 for 1 hour Fire Rated 18mil VersaDry Track w/ 1 layer of Impact Resistant Gypsum
- STC = 53 for 2 hour Fire Rated 18mil VersaDry Track w/ 2 layers of 5/8" Type X Gypsum

CLICK HERE TO WATCH THE VIDEO



INNOVATION, SERVICE, QUALITY

www.BuildStrong.com • 1-866-372-6384






VERSADRY TRACK SYSTEM



1-PIECE DESIGN



1 layer of Gypsum on 1 side




2 layers of Gypsum on 1 side
1 layer of Gypsum on opposite side

1 layer of Gypsum on 2 sides

2 layers of Gypsum on 2 sides

VersaDry with Clip Assembly - US PATENT 12,428,837

VersaDry Clip - US Patent 2026-0015858




VersaDry with clip at floor or ceiling without caulk

US PATENT 8,596,019

2-PIECE DESIGN


US PATENT 10,487,497




195-NRVDT2

125-1HRVDT2


125-2HRVDT2



Non-Rated



1 Hour Fire Rated



2 Hour Fire Rated



INNOVATION, SERVICE, QUALITY

www.BuildStrong.com • 1-866-372-6384

